Schedule of articles—*concld.*

No.	Description of articles	Probable quantity required	Per
56	J. K. Black ink No. 2	300 lbs. ...	lb.
57	Coloured printing ink (in ½ lb. tins.)	20 „ ...	„
58	Litho black ink No. 50 (in 1 lb. tins) ...	10 „ ...	„
59	J. K. black ink No. 9 (in 1 lb. tins)	30 „ ...	„
60	Vermilion steel plate ink No. 922	16 „ ...	„
61	Royal blue No. 929	16 „ ...	„
62	Litho varnish (thin)	4 tins ...	Tin.
63	Do (middle)	4 „ ...	„
64	Spindle oil	96 gallons ...	Gallon.
65	Type metal (English some approved make) ...	1 ton ...	Ton.
66	Cylinder impression cloth	20 yards ...	Yard.
67	Composing sticks ten inches whipper jobbing ...	1 dozen ...	Dozen.
68	Litho transfer paper	10 quires ...	Quire.
69	Machine cotton	500 reels ...	Dozen.
70	Brass rules (1½ pt.)	25 gross ...	Gross.
71	1½ pt. lead	5 cwt. ...	Cwt.
72	1 pt. lead	1 „ ...	„
73	Type cases	2 dozens ...	Dozen.

D. B. RAMACHANDRA MUDALIAR,
Superintendent.

SANDAL OIL FACTORY, MYSORE.

Dated 30th January 1920.

It is hereby notified that sealed tenders will be received at the office of the Superintendent, Sandal Oil Factory, Mysore, for constructing quarters estimated at about Rs. 60,000 in the premises of the Sandal Oil Factory, Mysore, the latest date for receipt of such tenders being 15th February 1920.

2. The estimate of quantities is not given as which of the buildings estimated at over five lakhs will be taken up first is not known. The sum of Rs. 60,000 mentioned above should be expended before the end of June 1920.

3. All rates to be quoated for first class materials and workmanship.

4. The plans of the quarters may be seen in the office of the Superintendent, Sandal Oil Factory, between 11 A.M. and 5 P.M., on all office days.

5. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

6. The tender must be accompanied by a deposit of Rs. 100 in cash as earnest money and be superscribed. "*Tender for constructing quarters in the premises of the Sandal Oil Factory*," in default of which, tenders will be rejected.

7. The final acceptance of the tender will rest with the Superintendent, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

8. Within eight days of the acceptance of the tender, the successful competitor whose name will be noted on the notice board at the Factory, will be required to execute an agreement for taking up the construction work and finishing it before the time to be fixed by the Superintendent. In default his tender will be cancelled and his earnest money forfeited.

9. The earnest money on rejected tenders will be returned at the cost of tenderers.

Serial No.	Items of work	Unit	Rate	Remarks
			Rs. a. p.	
1	Earthwork excavation and filling basement ...	C. yd.		
2	Lime concrete foundation	C. ft.		
3	Foundation and basement with brick in mortar ...	,,		
4	Superstructure with brick in mortar ground floor ...	,,		
	Do do first floor ...	,,		
	Do with brick in mud ground floor ...	,,		
5	Semi-circular arch work brick in mortar ...	,,		
6	Segmental do do	,,		
7	Cornice, 9″×6″ do	R. ft.		
8	Ordinary parapet wall including pillasters and plastering, complete.	,,		
9	Flooring with first class 9″ sq. tiles over 4½″ concrete and cement pointing.	Sq.		
10	Do Cuddappa slabs do ...	,,		
11	Gravel flooring	,,		
12	Roofing with first class Mangalore tiles on teak reepers 2″×1″ including wood oiling :—			
	(*a*) With ceiling tiles	,,		
	(*b*) Without ceiling tiles	,,		
13	Ridge tiles set in mortar and cement pointing ...	R. ft.		
14	Flat terrace, pukkah	Sq.		
15	Plastering with chunam	,,		
16	Teakwood work wrought and put up	C. ft.		
17	Weather board ¾″×9″ including painting ...	R. ft.		
18	Do do ornamental do ...	,,		
19	Teakwood doors panelled with top glazed ventilators, bars with complete fittings.	S. ft.		
20	Teakwood doors panelled with all fittings complete	,,		
21	Teakwood doors battened do ...	,,		
22	Teakwood windows with double shutters glazed and with top glazed ventilators and iron fittings, etc., complete.	,,		
23	Teakwood windows without ventilators do ...	S. ft.		
24	Teakwood windows battened with iron fittings, complete.	,,		
25	Glazed ventilators barred with hooksa nd ropes, complete.	,,		
26	Cub boards with panelled shutters with complete fittings, etc.	,,		
27	Silicate painting two coats for doors and windows ...	Sq.		
28	White and colourwashing, two coats	,,		
29	Burnt stone slabs for lintel and bed plate ...	S. ft.		
30	Do for steps with two lines dressing ...	,,		
31	Zinc sheets for valleys with cement and mortar bands	,,		
32	Finials for gables 4′	Each		
33	Terminals 2½′	,,		
34	Wood oiling, two coats	Sq.		
35	Mortar bands for roofing	R. ft.		
36	Zinc sheet down pipes 3″ dia.	,,		
37	4½″ thick concrete flooring and plastering ...	Sq.		
38	Earthwork levelling ground	C. yd.		
39	Clearing site	S. yd.		

N. B.—The contractor will have to accept any materials supplied departmentally at ruling market rates.

N. SUBBA RAO,
Superintendent.